



**ROBERTS**  
CIVIL ENGINEERING

301 Sea Island Road Suite 10, St. Simons Island, GA 31522  
912-638-9681 Office

October 27, 2020

**Owner:** City of Darien  
106 Washington Street  
Darien, GA 31305

**Re:** City of Darien 2018-2020 LMIG Projects- Market St. Ext., RFP No. 374

**Addendum No. 6**

**Pre-Proposal Conference and Proposal Due Date Confirmation:**

The non-mandatory Pre-Proposal Conference for this project is **Thursday, October 29, 2020 at 11:00 a.m.** The Proposal deadline will be **Thursday, November 12, 2020 at 2:00 p.m.** Both will take place at the Darien City Hall located at 106 Washington Street, Darien, Georgia 31305. The RFP shows a different date however, Addendum No. 5 was intended to replace those dates.

**Deadline for questions:**

The last day for questions will be **Friday, November 6, 2020.** You may email your questions to Jessica Najjar at [jnajar@robertscivilengineering.com](mailto:jnajar@robertscivilengineering.com).

**Proposal Sheet:**

The **Line Item No.** column on the Proposal Sheet was incorrectly formatted. Please use the attached revised Proposal Sheet to replace pages 17-19 of the RFP and note that the remainder of the sheet did not change.

Technical Contact:  
Jeff Bors  
Project Manager  
912-638-9681  
[jbors@robertscivilengineering.com](mailto:jbors@robertscivilengineering.com)

## PROPOSAL SHEET

FROM: \_\_\_\_\_

<b>Project: Market Street</b>	<b>L X W: Approximately 1302' X 22'</b>
<b>From: End of Pavement</b>	<b>To: Gray Street</b>

Line Item No.	DOT Ref. No.	Item Description	Qty	Unit	Unit Price	Amount
1.	150	Traffic Control	1	LS		
2.	151	Mobilization	1	LS		
3.	201	Clearing and Grubbing of Right of Way	1.4	AC		
4.	210	Grading Complete	1	LS		
5.	205	Removal of Unsuitable Soils	1,361	CY		
6.	209	Imported Structural Fill (Placed)	1885	CY		
7.	205	Asphalt Paving Demolition and Removal (including sawcut)	122	SY		
8.	310	6" Crushed Lime Rock or Aggregate Base	4142	SY		
9.	400	1.5" Asphalt Surface Course 12.5mm Superpave	330	TN		
10.	706	Turf Establishment	1.2	AC		
11.	163	Erosion and Sediment Control	1	LS		
12.		Water Main Pipe 8"Ø C900 DR18	1,610	LF		
13.		Water Main Pipe 3"Ø C900 DR18	10	LF		
14.		Water Main Pipe 8"Ø HDPE DR11	45	LF		
15.		Fire Hydrants Assemblies	4	EA		
16.		1" Tapping Saddle for Lateral Connections	27	EA		
17.		8" Tapping Saddle with Valve	1	EA		
18.		8" Tapping Tee	1	EA		
19.		3" Tapping Saddle	1	EA		
20.		1" Polyethylene Lateral Tubing	920	LF		
21.		8" Flush Valve	1	EA		

22.		Mechanical Fittings	3	EA		
23.		Water Main Connection	1	EA		
24.		Water System Testing	1	LS		
25.		Gravity Sanitary Sewer Pipe 8" SDR-26	1558	LF		
26.	668	Sanitary Sewer Manhole, Type 1	6	EA		
27.		Coring Manhole	1	EA		
28.		8" 45° Mechanical Joint Bend	2	EA		
29.		8" 11.25° Mechanical Joint Bend	1	EA		
30.		8" x 3" Mechanical Joint Reducer	1	EA		
31.		Sanitary Sewer Service Connections	1	EA		
32.		Sanitary Sewer Services	31	EA		
33.		Sewer Testing	1	LS		
34.		8" C.O.	31	EA		
35.	R-1	Stop Sign (Installed incl. post)	1	EA		
36.	R2-1	Speed Limit Sign (25 m.p.h.) (installed incl. post)	2	EA		
37.	OM-3R	Black on Yellow Sign (Installed incl. post)	1	EA		
38.	OM-3L	Black on Yellow Sign (Installed incl. post)	1	EA		
39.	W1-7	Two Direction Arrow Sign	1	EA		
40.	652	5" Solid Traffic Stripe- White	2864	LF		
41.	652	5" Solid Traffic Stripe- Yellow	1432	LF		
42.	652	5" Skip Traffic Stripe- Yellow	1432	GLF		
43.	550	RCP #1: Elliptical Pipe 14" x 23"	63	LF		
44.	550	#2: Storm Drain Pipe 18" HDPE	30	LF		
45.	550	Flared-end section 23" Elliptical RCP	2	EA		
46.	708	Plant Topsoil (2" depth, 2' width on shoulder)	40	CY		
47.	603	Rip Rap Type 3	36	SY		
48.	163	Erosion Control	1	LS		

49.	201	Concrete Sidewalk Demolition and Removal (including sawcut)	1	LS		
50.	441	4" Concrete Sidewalk	7	SY		
51.		Write-In				
52.		Write-In				

**TOTAL \$\_\_\_\_\_**

*Note:*

*Georgia Department of Transportation Standard Specification will apply unless otherwise specified  
The Contractor shall write "no bids" in all appropriate spaces.*